

ACS Flex 3 -

Installed Cost Comparison

Backup	Pipe & Wire			Flex 3 by ACS		
	Materials	\$	Labor (hours)	Materials	\$	Labor (hours)
1 High Bay Fixture						
Industrial space; 2 circuits; 25' centers	25' conduit 3/4 EMT + 2 couplings	7.46	1.00	1 - 2EB25	26.51	0.20
35' ceiling; panel switching; 8 fixtures per row	100' THHN black stranded	6.50	0.40	5 - Caddy supports	1.50	0.20
	2 - 3/4 steel connectors	0.66	0.10	1 - C2LA03	8.00	0.05
	2 - caddy supports	1.92	0.15	1 - 2PHA	7.42	0.05
	1 - Raco 4 x 2-1/8 box	1.79	0.70	1 - Pre-wire C2LA03		
	1 - 18/3 Hubbell plug & receptacle	11.65	0.30	by fixture manufact	5.00	0.00
	1 - Fixture Hook	5.00	0.00	1 - Fixture hook pre-wire	5.00	0.00
TOTAL		\$34.98	2.65 hrs.		\$53.43	0.50 hrs.